1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Issue Date (YYYY.MM.DD)	Reference:	Required Date (YYYY.MM.DD)
2025.11.13	**F-1125 F-1126 F-1127 F-1128**	**2026.05.15**
Shipping Instructions	FOB	Payment Terms
Sea Prepaid and Charge	**DDP USA PORT**	**See Below**

VENDOR:

LACQUERCRAFT HOSPITALITY
2575 PENNY ROAD
HIGH POINT NC 27265
UNITED STATES

CORY BRANCH 336-822-8084
CBRANCH@LACQUERCRAFTHOSPITALITY.COM

SHIP TO:

BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)
TO BE DETERMINED

INVOICE TO:

MGM RESORTS DESIGN & DEVELOPMENT
C/O THE CARDY GROUP
1220 YONGE ST - SUITE 300
TORONTO ON M4T 1W1
CANADA

***Invoices to be addressed to Legal Entity above**

Note: All Instructions must be followed or merchandise will not be accepted:

1. Acceptance of this order constitutes acceptance of all terms and conditions as attached.
2. Purchase order number must be shown on all packing slips,shipping documents and invoices.

PURCHASE ORDER PROOF ONLY

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
2,211.00	**EACH**	**1251-006-0092 30"W Nightstand**	**F-1125**	**303.60**	**671,259.60**

***TOTAL ORDERED QTY IS 2211**
QTY BREAKDOWN: 2200 + 11 SPARE

COST BREAKDOWN:
$264.00 + $39.60 TARIFF PER ITEM = $303.60 TOTAL COST PER ITEM

***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER

PER AVENUE ID SPECIFICATION DATED 05.30.25 - NOTE: ELECTRICAL COSTS NOT INCLUDED IN THIS ORDER, ALL ELECTRICAL COMPONENTS ARE ORDERED ON PO 1251-0063 AND TO BE SHIPPED SEPARATELY, NOT WITH UNITS.

ITEM NAME/NO.: CUSTOM NIGHTSTAND
DIMENSIONS: OVERALL - 30"W X 18"D X 27"H; TOE KICK - 3"H
DESCRIPTION: CUSTOM NIGHTSTAND WITH INSET STONE TOP AND WOOD TRIM AT PERIMETER, RADIUSED CORNERS AT ALL SIDES, AND WOOD TOE KICK. STONE TOP TO SIT PROUD OF WOOD PERIMETER. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. NIGHTSTAND TO INCLUDE (1) DRAWER WITH FINGER PULL HARDWARE AND (1) OPEN CUBBY WITH INTEGRATED LED DOWNLIGHT. OPEN CUBBY TO HAVE A METAL BACK PANEL AND WOOD SIDE PANELS. EDGES OF ALL METAL DETAILS MUST BE EASED. LIGHT CHANNEL TO HAVE FROSTED ACRYLIC DIFFUSER FOR EVEN LIGHT SPREAD WITH NO HOT SPOTS, SHADOWS, OR GAPS. CUBBY DOWNLIGHT TO BE OPERATED BY 3-WAY SWITCH ON HEADBOARD AND SWITCH ON/OFF SIMULTANEOUSLY WITH BED LIGHTS. MFR TO INSTALL SOFT-CLOSING MECHANISMS AT DRAWER TO ENSURE SAFE AND SMOOTH OPERATION. NIGHTSTAND TO SIT FLUSH AGAINST WOOD PANEL OF HEADBOARD AND SECURE TO HEADBOARD WITH CLEATS. OVERALL HEIGHT OF NIGHTSTAND TO BE 27". MFR TO PROVIDE PRE-PRODUCTION PHOTOS AND VIDEOS TO AVEID FOR REVIEW AND APPROVAL. REFER TO X-SHEET FOR DESIGN INTENT.
NOTE: MFR TO CONFIRM THAT LIGHTING CIRCUITRY FUNCTIONS AS DESCRIBED ABOVE. PHOTOS AND VIDEOS OF LIGHTS SWITCHING ON/OFF SIMULTANEOUSLY ARE REQUIRED AS PART OF THE PPS REPORT.

EXPOSED WOOD
SPECIES: OAK
CUT: QUARTERED
PORE: FILLED
FINISH: STAINED
COLOR: CUSTOM TO MATCH AVEID CONTROL SAMPLE
SHEEN: SATIN
DISTRESSING: NONE
SEALANT: PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
		EXPOSED METAL **FINISH:** PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE. **STONE TOP** PROVIDE 3/4" THICK CUSTOM QUARTZ TOP WITH EASED EDGE DETAIL. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. STONE TO SHIP SEPARATELY AND BE INSTALLED IN NIGHTSTAND ON SITE. REFER TO COMPONENT SPECS (F-1125A AND F-1125B) FOR ADDITIONAL INFORMATION. **DECORATIVE HARDWARE** CASE PIECE TO INCLUDE THE FOLLOWING DECORATIVE HARDWARE PIECES: MANUFACTURER: CASEGOOD MFR DIMENSIONS: 25-3/4"W X 1-3/4"D X 1/2"H DETAILS: FINGER PULL WITH ROLLED LIP FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE. QUANTITY: 1 PER NIGHTSTAND REFER TO X-SHEETS FOR EXACT LOCATION, DIMENSIONS, AND DESIGN INTENT. HARDWARE SHALL BE PROVIDED AND INSTALLED BY MFR PER AVEID SPECIFICATION. ALL VISIBLE HARDWARE USED IS TO MATCH THE DECORATIVE HARDWARE FINISH. FASTENERS MUST NOT BE EXPOSED. ALL FACE SCREWS MUST BE COUNTERSUNK. MFR TO PROVIDE LOCK WASHERS (SPLIT OR SERRATED) FOR ALL HARDWARE TO PREVENT KNOBS FROM SPINNING. MFR TO SUPPLY APPROPRIATE LOCKING MECHANISM AS APPLICABLE PER DRAWING. MUST BE HAFELE OR EQUAL. MFR TO SUPPLY APPROPRIATE MAGNETIC DOOR CATCHES AS APPLICABLE, MUST BE HAFELE OR EQUAL, CONFIRM DETAILS WITH AVEID. **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO. **TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)** **SPECIFICATION:F-1125** **DESCRIPTION: 30"W NIGHTSTAND** **2211 EACH**			
1,580.00	**EACH**	**1251-006-0093 Stone Top @ 30"W King Nightstand**	**F-1125A**	**127.65**	**201,687.00**
		***TOTAL ORDERED QTY IS 1580** QTY BREAKDOWN: 1572 + 8 SPARE **COST BREAKDOWN:** $111.00 + $16.65 TARIFF PER ITEM = $127.65 TOTAL COST PER ITEM ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER **PER AVENUE ID SPECIFICATION DATED 05.30.25** **ITEM NAME/NO.:** CUSTOM QUARTZ TOP **COLOR/FINISH:** CALACATTA VIOLA / POLISHED **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1125 **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA VIOLA MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT PERIMETER OF F-1125 NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS. **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED STONE ON TABLETOP. **STONE CONSTRUCTION** STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP. **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN KING GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS. **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO. **TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)** **SPECIFICATION:F-1125A** **DESCRIPTION: STONE TOP @ 30"W KING NIGHTSTAND** **1580 EACH**			
631.00	**EACH**	**1251-006-0094 Stone Top @ 30"W Queen Nightstand**	**F-1125B**	**0.00**	**0.00**

PURCHASE ORDER PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:

MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)

*****ITEM DELETED DUE TO REJECTED CALACATTA TUCCI QUARTZ SLAB IMAGES FROM LACQUERCRAFT. DESIGN REQUESTED TO SOURCE THIS STONE FROM ONE SOURCE SO KIMBALL HOSPITALITY TO SUPPLY FINISHED NIGHTSTAND STONE TOPS USING THEIR CALACATTA TUCCI QUARTZ. LACQUERCRAFT TO PROVIDE WOODEN TEMPLATE TO KIMBALL AND KIMBALL TO PROVIDE LACQUERCRAFT WITH A PRE-PRODUCTION SAMPLE TO CHECK FITMENT.**

THE FOLLOWING HAS BEEN DELETED:
[DELETED] ***TOTAL ORDERED QTY IS 631**
[DELETED] QTY BREAKDOWN: 628 + 3 SPARE
[DELETED]
[DELETED] **COST BREAKDOWN:**
[DELETED] $102.00 + $15.30 TARIFF PER ITEM = $117.30 TOTAL COST PER ITEM
[DELETED]
[DELETED] ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER
[DELETED]
[DELETED] **PER AVENUE ID SPECIFICATION DATED 05.30.25**
[DELETED]
[DELETED]
[DELETED] **ITEM NAME/NO.:** CUSTOM QUARTZ TOP
[DELETED] **COLOR/FINISH:** CALACATTA TUCCI / POLISHED
[DELETED] **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1125
[DELETED] **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA TUCCI MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED
[DELETED] GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT
[DELETED] PERIMETER OF F-1125 NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE
[DELETED] WITHIN +/- 1MM TOLERANCE.
[DELETED] **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.
[DELETED] **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED
[DELETED] STONE ON TABLETOP.
[DELETED]
[DELETED] **STONE CONSTRUCTION**
[DELETED] STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO
[DELETED] BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP.
[DELETED]
[DELETED] **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN DOUBLE QUEEN GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS.
[DELETED]

[DELETED] **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO.

100.00	**EACH**	**1251-006-0095 24"W Nightstand (1 Ea per Guestroom)**	**F-1126**	**285.20**	**28,520.00**

***TOTAL ORDERED QTY IS 100**
QTY BREAKDOWN: 99 + 1 SPARE

COST BREAKDOWN:
$248.00 + $37.20 TARIFF PER ITEM = $285.20 TOTAL COST PER ITEM

***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER

PER AVENUE ID SPECIFICATION DATED 05.30.25 - NOTE: ELECTRICAL COSTS NOT INCLUDED IN THIS ORDER, ALL ELECTRICAL COMPONENTS ARE ORDERED ON PO 1251-0063 AND TO BE SHIPPED SEPARATELY, NOT WITH UNITS.

ITEM NAME/NO.: CUSTOM NIGHTSTAND
DIMENSIONS: OVERALL - 24"W X 18"D X 27"H; TOE KICK - 3"H
DESCRIPTION: CUSTOM NIGHTSTAND WITH INSET STONE TOP AND WOOD TRIM AT PERIMETER, RADIUSED CORNERS AT ALL SIDES, AND WOOD TOE KICK. STONE TOP TO
SIT PROUD OF WOOD PERIMETER. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. NIGHTSTAND TO INCLUDE (1) DRAWER WITH FINGER PULL
HARDWARE AND (1) OPEN CUBBY WITH INTEGRATED LED DOWNLIGHT. OPEN CUBBY TO HAVE A METAL BACK PANEL AND WOOD SIDE PANELS. EDGES OF ALL METAL
DETAILS MUST BE EASED. LIGHT CHANNEL TO HAVE FROSTED ACRYLIC DIFFUSER FOR EVEN LIGHT SPREAD WITH NO HOT SPOTS, SHADOWS, OR GAPS. CUBBY DOWNLIGHT TO BE OPERATED BY 3-WAY SWITCH ON HEADBOARD AND SWITCH ON/OFF SIMULTANEOUSLY WITH BED LIGHTS. MFR TO INSTALL SOFT-CLOSING MECHANISMS AT DRAWER TO ENSURE SAFE AND SMOOTH OPERATION. NIGHTSTAND TO SIT FLUSH AGAINST WOOD PANEL OF HEADBOARD AND SECURE TO HEADBOARD WITH CLEATS. OVERALL HEIGHT OF NIGHTSTAND TO BE 27". MFR TO PROVIDE PRE-PRODUCTION PHOTOS AND VIDEOS TO AVEID

PURCHASE ORDER PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)

FOR REVIEW AND APPROVAL. REFER TO X-SHEET FOR DESIGN INTENT. NOTE: MFR TO CONFIRM THAT LIGHTING CIRCUITRY FUNCTIONS AS DESCRIBED ABOVE. PHOTOS AND VIDEOS OF LIGHTS SWITCHING ON/OFF SIMULTANEOUSLY ARE REQUIRED AS PART OF THE PPS REPORT.

EXPOSED WOOD
SPECIES: OAK
CUT: QUARTERED
PORE: FILLED
FINISH: STAINED
COLOR: CUSTOM TO MATCH AVEID CONTROL SAMPLE
SHEEN: SATIN
DISTRESSING: NONE
SEALANT: PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.

EXPOSED METAL
FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE.

STONE TOP
PROVIDE 3/4" THICK CUSTOM QUARTZ TOP WITH EASED EDGE DETAIL. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. THICKNESS MUST
BE WITHIN +/- 1MM TOLERANCE. STONE TO SHIP SEPARATELY AND BE INSTALLED IN NIGHTSTAND ON SITE. REFER TO COMPONENT SPECS (F-1126A) FOR ADDITIONAL
INFORMATION.

DECORATIVE HARDWARE
CASE PIECE TO INCLUDE THE FOLLOWING DECORATIVE HARDWARE PIECES:
MANUFACTURER: CASEGOOD MFR
DIMENSIONS: 19-3/4"W X 1-3/4"D X 1/2"H
DETAILS: FINGER PULL WITH ROLLED LIP
FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE.
QUANTITY: 1 PER NIGHTSTAND
REFER TO X-SHEETS FOR EXACT LOCATION, DIMENSIONS, AND DESIGN INTENT.
HARDWARE SHALL BE PROVIDED AND INSTALLED BY MFR PER AVEID SPECIFICATION. ALL VISIBLE HARDWARE USED IS TO MATCH THE DECORATIVE HARDWARE FINISH.
FASTENERS MUST NOT BE EXPOSED. ALL FACE SCREWS MUST BE COUNTERSUNK.
MFR TO PROVIDE LOCK WASHERS (SPLIT OR SERRATED) FOR ALL HARDWARE TO PREVENT KNOBS FROM SPINNING.
MFR TO SUPPLY APPROPRIATE LOCKING MECHANISM AS APPLICABLE PER DRAWING. MUST BE HAFELE OR EQUAL.
MFR TO SUPPLY APPROPRIATE MAGNETIC DOOR CATCHES AS APPLICABLE, MUST BE HAFELE OR EQUAL, CONFIRM DETAILS WITH AVEID.

NOTE: SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO.

TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)
SPECIFICATION:F-1126
DESCRIPTION: 24"W NIGHTSTAND (1 EA PER GUESTROOM)
100 EACH

100.00	**EACH**	**1251-006-0096 Stone Top @ 24"W Queen Nightstand**	**F-1126B**	**0.00**	**0.00**

*****ITEM DELETED DUE TO REJECTED CALACATTA TUCCI QUARTZ SLAB IMAGES FROM LACQUERCRAFT. DESIGN REQUESTED TO SOURCE THIS STONE FROM ONE SOURCE SO KIMBALL HOSPITALITY TO SUPPLY FINISHED NIGHTSTAND STONE TOPS USING THEIR CALACATTA TUCCI QUARTZ. LACQUERCRAFT TO PROVIDE WOODEN TEMPLATE TO KIMBALL AND KIMBALL TO PROVIDE LACQUERCRAFT WITH A PRE-PRODUCTION SAMPLE TO CHECK FITMENT.**

THE FOLLOWING HAS BEEN DELETED:

[DELETED] ***TOTAL ORDERED QTY IS 100**
[DELETED] QTY BREAKDOWN: 99 + 1 SPARE
[DELETED]
[DELETED] **COST BREAKDOWN:**
[DELETED] $90.00 + $13.50 TARIFF PER ITEM = $103.50 TOTAL COST PER ITEM
[DELETED]
[DELETED] ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER
[DELETED]
[DELETED] **PER AVENUE ID SPECIFICATION DATED 05.30.25**
[DELETED]
[DELETED] **ITEM NAME/NO.:** CUSTOM QUARTZ TOP
[DELETED] **COLOR/FINISH:** CALACATTA TUCCI / POLISHED
[DELETED] **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1126
[DELETED] **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA TUCCI MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED
[DELETED] GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT

PURCHASE ORDER PROOF ONLY

The Cardy Group
1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)

[DELETED] PERIMETER OF F-1126 NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE
[DELETED] WITHIN +/- 1MM TOLERANCE.
[DELETED] **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.
[DELETED] **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED
[DELETED] STONE ON TABLETOP.
[DELETED]
[DELETED] **STONE CONSTRUCTION**
[DELETED] STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO
[DELETED] BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP.
[DELETED]
[DELETED] **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN DOUBLE QUEEN GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS.

[DELETED] **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO.

86.00	EACH	1251-006-0097 30"W ADA Nightstand	F-1127	341.55	29,373.30

***TOTAL ORDERED QTY IS 86**
QTY BREAKDOWN: 85+ 1 SPARE

COST BREAKDOWN:
$252.00 + $37.80 TARIFF PER ITEM = $289.80 TOTAL COST PER ITEM
COST REVISED TO REFLECT CHANGES IN DESIGN DUE TO ADA REQUIREMENTS: NEW COST $297 + $44.55 = $341.55

***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER

PER AVENUE ID REV 1 SPECIFICATION DATED 12.08.2025 - REVISED DESIGN REPLACES OPEN CUBBY WITH BOTTOM DRAWER TO ENSURE ADA COMPLIANCE

NOTE: ELECTRICAL COSTS NOT INCLUDED IN THIS ORDER, ALL ELECTRICAL COMPONENTS ARE ORDERED ON PO 1251-0063 AND TO BE SHIPPED SEPARATELY, NOT WITH UNITS.

ITEM NAME/NO.: CUSTOM ADA NIGHTSTAND
DIMENSIONS: OVERALL - 30"W X 18"D X 23"H; TOE KICK - 3"H
DESCRIPTION: CUSTOM ADA NIGHTSTAND WITH INSET STONE TOP AND WOOD TRIM AT PERIMETER, RADIUSED CORNERS AT ALL SIDES, AND WOOD TOE KICK WITH INTEGRATED LED DOWNLIGHT. STONE TOP TO SIT PROUD OF WOOD PERIMETER. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. NIGHTSTAND TO INCLUDE (2) DRAWERS WITH ADA- COMPLIANT FINGER PULL HARDWARE. EDGES OF ALL METAL DETAILS MUST BE EASED. LIGHT CHANNEL TO HAVE FROSTED ACRYLIC DIFFUSER FOR EVEN LIGHT SPREAD WITH NO HOT SPOTS, SHADOWS, OR GAPS. TOE KICK DOWNLIGHT TO BE OPERATED BY 3-WAY SWITCH ON HEADBOARD AND SWITCH ON/OFF SIMULTANEOUSLY WITH BED LIGHTS. MFR TO INSTALL SOFT-CLOSING MECHANISMS AT DRAWERS TO ENSURE SAFE AND SMOOTH OPERATION. NIGHTSTAND TO SIT FLUSH AGAINST WOOD PANEL OF HEADBOARD AND SECURE TO HEADBOARD WITH CLEATS. OVERALL HEIGHT OF NIGHTSTAND TO BE 23". MFR TO PROVIDE PRE-PRODUCTION PHOTOS AND VIDEOS TO AVEID FOR REVIEW AND APPROVAL. REFER TO X-SHEET FOR DESIGN INTENT.
NOTE: MFR TO CONFIRM THAT LIGHTING CIRCUITRY FUNCTIONS AS DESCRIBED ABOVE. PHOTOS AND VIDEOS OF LIGHTS SWITCHING ON/OFF SIMULTANEOUSLY ARE REQUIRED AS PART OF THE PPS REPORT.

EXPOSED WOOD
SPECIES: OAK
CUT: QUARTERED
PORE: FILLED
FINISH: STAINED
COLOR: CUSTOM TO MATCH AVEID CONTROL SAMPLE
SHEEN: SATIN
DISTRESSING: NONE
SEALANT: PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.

EXPOSED METAL
FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE.
SEALANT: PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS.

DECORATIVE HARDWARE
CASE PIECE TO INCLUDE THE FOLLOWING DECORATIVE HARDWARE PIECES:
MANUFACTURER: CASEGOOD MFR

USER PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
		DIMENSIONS: 25-3/4"W X 2"D X 1"H DETAILS: ADA-COMPLIANT FINGER PULL WITH ROLLED LIP FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE. QUANTITY: 2 PER NIGHTSTAND REFER TO X-SHEETS FOR EXACT LOCATION, DIMENSIONS, AND DESIGN INTENT. HARDWARE SHALL BE PROVIDED AND INSTALLED BY MFR PER AVEID SPECIFICATION. ALL VISIBLE HARDWARE USED IS TO MATCH THE DECORATIVE HARDWARE FINISH. FASTENERS MUST NOT BE EXPOSED. ALL FACE SCREWS MUST BE COUNTERSUNK. MFR TO PROVIDE LOCK WASHERS (SPLIT OR SERRATED) FOR ALL HARDWARE TO PREVENT KNOBS FROM SPINNING. MFR TO SUPPLY APPROPRIATE LOCKING MECHANISM AS APPLICABLE PER DRAWING. MUST BE HAFELE OR EQUAL. MFR TO SUPPLY APPROPRIATE MAGNETIC DOOR CATCHES AS APPLICABLE, MUST BE HAFELE OR EQUAL, CONFIRM DETAILS WITH AVEID. **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO. **TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)** **SPECIFICATION:F-1127** **DESCRIPTION: 30"W ADA NIGHTSTAND** **85 EACH**			
70.00	**EACH**	**1251-006-0099 Stone Top @ 30"W King ADA Nightstand**	**F-1127A**	**141.45**	**9,901.50**
		***TOTAL ORDERED QTY IS 70** QTY BREAKDOWN: 68 + 2 SPARE **COST BREAKDOWN:** $123.00 + $18.45 TARIFF PER ITEM = $141.45 TOTAL COST PER ITEM ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER **PER AVENUE ID SPECIFICATION DATED 05.30.25** **ITEM NAME/NO.:** CUSTOM QUARTZ TOP **COLOR/FINISH:** CALACATTA VIOLA / POLISHED **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1127 **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA VIOLA MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT PERIMETER OF F-1127 ADA NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS. **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED STONE ON TABLETOP. **STONE CONSTRUCTION** STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP. **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN KING GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS. **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO. **TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)** **SPECIFICATION:F-1127A** **DESCRIPTION: STONE TOP @ 30"W KING ADA NIGHTSTAND** **68 EACH**			
18.00	**EACH**	**1251-006-0098 Stone Top @ 30"W Queen ADA Nightstand**	**F-1127B**	**0.00**	**0.00**
		*****ITEM DELETED DUE TO REJECTED CALACATTA TUCCI QUARTZ SLAB IMAGES FROM LACQUERCRAFT. DESIGN REQUESTED TO SOURCE THIS STONE FROM ONE SOURCE SO KIMBALL HOSPITALITY TO SUPPLY FINISHED NIGHTSTAND STONE TOPS USING THEIR CALACATTA TUCCI QUARTZ. LACQUERCRAFT TO PROVIDE WOODEN TEMPLATE TO KIMBALL AND KIMBALL TO PROVIDE LACQUERCRAFT WITH A PRE-PRODUCTION SAMPLE TO CHECK FITMENT.** **THE FOLLOWING HAS BEEN DELETED:** [DELETED] ***TOTAL ORDERED QTY IS 18**			

PURCHASE ORDER PROOF ONLY

The Cardy Group
1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
		[DELETED] QTY BREAKDOWN: 17 + 1 SPARE [DELETED] [DELETED] **COST BREAKDOWN:** [DELETED] $113.00 + $16.95 TARIFF PER ITEM = $129.95 TOTAL COST PER ITEM [DELETED] [DELETED] ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER [DELETED] [DELETED] **PER AVENUE ID SPECIFICATION DATED 05.30.25** [DELETED] [DELETED] **ITEM NAME/NO.:** CUSTOM QUARTZ TOP [DELETED] **COLOR/FINISH:** CALACATTA TUCCI / POLISHED [DELETED] **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1127 [DELETED] **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA TUCCI MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED [DELETED] GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT [DELETED] PERIMETER OF F-1127 ADA NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. [DELETED] **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS. [DELETED] **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED [DELETED] STONE ON TABLETOP [DELETED] [DELETED] **STONE CONSTRUCTION** [DELETED] STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO [DELETED] BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP. [DELETED] [DELETED] **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN DOUBLE QUEEN GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS. [DELETED] [DELETED] **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO.			
4.00	**EACH**	**1251-006-0101 16"W Nightstand (2 Ea per Guestroom)**	**F-1128**	**382.95**	**1,531.80**
		***TOTAL ORDERED QTY IS 4** NO SPARE **COST BREAKDOWN:** $333.00 + $49.95 TARIFF PER ITEM = $382.95 TOTAL COST PER ITEM ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER **PER AVENUE ID SPECIFICATION DATED 05.30.25 - NOTE: ELECTRICAL COSTS NOT INCLUDED IN THIS ORDER, ALL ELECTRICAL COMPONENTS ARE ORDERED ON PO 1251-0063 AND TO BE SHIPPED SEPARATELY, NOT WITH UNITS.** **ITEM NAME/NO.:** CUSTOM NIGHTSTAND DIMENSIONS: OVERALL - 16"W X 18"D X 27"H; TOE KICK - 3"H DESCRIPTION: CUSTOM NIGHTSTAND WITH INSET STONE TOP AND WOOD TRIM AT PERIMETER, RADIUSED CORNERS AT ALL SIDES, AND WOOD TOE KICK. STONE TOP TO SIT PROUD OF WOOD PERIMETER. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. NIGHTSTAND TO INCLUDE (1) DRAWER WITH FINGER PULL HARDWARE AND (1) OPEN CUBBY WITH INTEGRATED LED DOWNLIGHT. OPEN CUBBY TO HAVE A METAL BACK PANEL AND WOOD SIDE PANELS. EDGES OF ALL METAL DETAILS MUST BE EASED. LIGHT CHANNEL TO HAVE FROSTED ACRYLIC DIFFUSER FOR EVEN LIGHT SPREAD WITH NO HOT SPOTS, SHADOWS, OR GAPS. CUBBY DOWNLIGHT TO BE OPERATED BY 3-WAY SWITCH ON HEADBOARD AND SWITCH ON/OFF SIMULTANEOUSLY WITH BED LIGHTS. MFR TO INSTALL SOFT-CLOSING MECHANISMS AT DRAWER TO ENSURE SAFE AND SMOOTH OPERATION. NIGHTSTAND TO SIT FLUSH AGAINST WOOD PANEL OF HEADBOARD AND SECURE TO HEADBOARD WITH CLEATS. OVERALL HEIGHT OF NIGHTSTAND TO BE 27". MFR TO PROVIDE PRE-PRODUCTION PHOTOS AND VIDEOS TO AVEID FOR REVIEW AND APPROVAL. REFER TO X-SHEET FOR DESIGN INTENT. NOTE: MFR TO CONFIRM THAT LIGHTING CIRCUITRY FUNCTIONS AS DESCRIBED ABOVE. PHOTOS AND VIDEOS OF LIGHTS SWITCHING ON/OFF SIMULTANEOUSLY ARE REQUIRED AS PART OF THE PPS REPORT. **EXPOSED WOOD** SPECIES: OAK CUT: QUARTERED PORE: FILLED FINISH: STAINED COLOR: CUSTOM TO MATCH AVEID CONTROL SAMPLE			

CASE GOODS PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
		SHEEN: SATIN DISTRESSING: NONE SEALANT: PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS. **EXPOSED METAL** FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE. **STONE TOP** PROVIDE 3/4" THICK CUSTOM QUARTZ TOP WITH EASED EDGE DETAIL. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. STONE TO SHIP SEPARATELY AND BE INSTALLED IN NIGHTSTAND ON SITE. REFER TO COMPONENT SPECS (F-1128A) FOR ADDITIONAL INFORMATION. **DECORATIVE HARDWARE** CASE PIECE TO INCLUDE THE FOLLOWING DECORATIVE HARDWARE PIECES: MANUFACTURER: CASEGOOD MFR DIMENSIONS: 11-3/4"W X 1-3/4"D X 1/2"H DETAILS: FINGER PULL WITH ROLLED LIP FINISH: PLATED BRUSHED BRASS - TO MATCH AVEID CONTROL SAMPLE. QUANTITY: 1 PER NIGHTSTAND REFER TO X-SHEETS FOR EXACT LOCATION, DIMENSIONS, AND DESIGN INTENT. HARDWARE SHALL BE PROVIDED AND INSTALLED BY MFR PER AVEID SPECIFICATION. ALL VISIBLE HARDWARE USED IS TO MATCH THE DECORATIVE HARDWARE FINISH. FASTENERS MUST NOT BE EXPOSED. ALL FACE SCREWS MUST BE COUNTERSUNK. MFR TO PROVIDE LOCK WASHERS (SPLIT OR SERRATED) FOR ALL HARDWARE TO PREVENT KNOBS FROM SPINNING. MFR TO SUPPLY APPROPRIATE LOCKING MECHANISM AS APPLICABLE PER DRAWING. MUST BE HAFELE OR EQUAL. MFR TO SUPPLY APPROPRIATE MAGNETIC DOOR CATCHES AS APPLICABLE, MUST BE HAFELE OR EQUAL, CONFIRM DETAILS WITH AVEID. **NOTE:** SHOP DRAWINGS AND FINISH SAMPLES MUST BE REVIEWED AND APPROVED BY DESIGN PRIOR TO PRODUCTION. PLEASE REFER TO THE END OF THE PURCHASE ORDER FOR SUBMITTAL INSTRUCTIONS, WOOD CONSTRUCTION, METAL CONSTRUCTION, STONE CONSTRUCTION AND GENERAL INFO. **TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)** **SPECIFICATION:F-1128** **DESCRIPTION: 16"W NIGHTSTAND (2 EA PER GUESTROOM)** **4 EACH**			
4.00	**EACH**	**1251-006-0102 Stone Top @ 16"W King Nightstand (2 Ea per Guestroom)**	**F-1128A**	**77.05**	**308.20**
		***TOTAL ORDERED QTY IS 4** NO SPARE **COST BREAKDOWN:** $67.00 + $10.05 TARIFF PER ITEM = $77.05 TOTAL COST PER ITEM ***REFER TO THE END OF THE PURCHASE ORDER FOR INSTRUCTIONS THAT APPLY TO ALL ITEMS NOTED ON THIS PURCHASE ORDER **PER AVENUE ID SPECIFICATION DATED 05.30.25** **ITEM NAME/NO.:** CUSTOM QUARTZ TOP **COLOR/FINISH:** CALACATTA VIOLA / POLISHED **DIMENSIONS:** PER NIGHTSTAND - REFER TO F-1128 **DESCRIPTION:** CUSTOM 3/4" THICK QUARTZ TOP INSPIRED BY CALACATTA VIOLA MARBLE WITH EASED EDGE DETAIL. STONE TOP TO FEATURE (1) U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. FINISH TO BE POLISHED. QUARTZ COLOR AND VEINING MUST BE THROUGH BODY. STONE TOP TO SIT PROUD OF WOOD TRIM AT PERIMETER OF F-1128 NIGHTSTAND. REFER TO NIGHTSTAND SPEC FOR ADDITIONAL INFORMATION. STONE TO BE INSTALLED IN NIGHTSTAND ON SITE. THICKNESS MUST BE WITHIN +/- 1MM TOLERANCE. **SEALANT:** PROVIDE CLEAR, PROTECTIVE, NON-YELLOWING SEALER TO WITHSTAND HEAT, ACID AND WATER STAINS. **GROMMET:** CASE PIECE TO INCLUDE (1) 1" X 1" U-SHAPED GROMMET CUTOUT FOR WIRE PASSAGE. INTERIOR EDGES OF CUTOUT TO BE FINISHED TO MATCH EXPOSED STONE ON TABLETOP. **STONE CONSTRUCTION** STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP. **INSTALLATION INSTRUCTIONS:** TO BE INSTALLED IN KING GUESTROOMS ONLY. REFER TO AVEID DRAWING SET FOR EXACT LOCATIONS.			

PURCHASE ORDER PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:
MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)

TAG: BORGATA MAIN TOWER ROOM REMODEL - PRODUCTION (C102317)
SPECIFICATION:F-1128A
DESCRIPTION: STONE TOP @ 16"W KING NIGHTSTAND (2 EA PER GUESTROOM)
4 EACH

*** IMPORTANT INSTRUCTIONS: THE FOLLOWING APPLIES TO ALL ITEMS NOTED ON THIS PURCHASE ORDER ***

*****OCEAN FREIGHT*****
OCEAN FREIGHT TO BE BILLED ON PURCHASE ORDER 1251-0064 FOR ALL ITEMS ORDERED ON THIS PURCHASE ORDER

THIS PURCHASE ORDER ASSUMES LACQUERCRAFT IS THE IMPORTER OF RECORD AND INCLUDES ANY APPLICABLE DUTIES AND OR TARIFFS.

****
PAYMENT TERMS: PER SIGNED PAYMENT BREAKDOWN SHEET DATED 11.07.2025 BY DOTTIE HAYWORTH
20% UPON ISSUANCE OF PURCHASE ORDER
20% UPON APPROVAL OF SHOP DRAWINGS, FINISH SAMPLES AND PROTO-TYPES
10% NET 30 UPON RECEIPT OF 20% OF GOODS, IN MIX OF PRODUCT APPROPRIATE TO TURNOVER COMPLETED FLOORS
10% NET 30 UPON RECEIPT OF 40% OF GOODS, IN MIX OF PRODUCT APPROPRIATE TO TURNOVER COMPLETED FLOORS
10% NET 30 UPON RECEIPT OF 60% OF GOODS, IN MIX OF PRODUCT APPROPRIATE TO TURNOVER COMPLETED FLOORS
10% NET 30 UPON RECEIPT OF 80% OF GOODS, IN MIX OF PRODUCT APPROPRIATE TO TURNOVER COMPLETED FLOORS
10% NET 30 UPON RECEIPT OF 100% OF GOODS, IN MIX OF PRODUCT APPROPRIATE TO TURNOVER COMPLETED FLOORS
10% NET 30 UPON RECONCILIATION OF ALL SHIPMENTS AND COMPLETION OF ANY PUNCH AND/OR REMEDIATION
****

THE FOLLOWING SUBMISSION AND PRODUCT INSTRUCTIONS TO BE APPLIED TO ALL ITEMS NOTED ON THIS PURCHASE ORDER

PLEASE SUBMIT THE FOLLOWING PRIOR TO PRODUCTION: SHOP DRAWINGS TO BE SUBMITTED VIA EMAIL TO:

MABEL.HAO@THECARDYGROUP.COM
ASHLEY.DERUSHA@THECARDYGROUP.COM
CLAIRE.CAULFIELD@THECARDYGROUP.COM
KRUPA.DESAI@THECARDYGROUP.COM
* SHOP DRAWINGS WILL BE DISTRIBUTED TO THE DESIGN TEAM VIA PROCORE BY THE CARDY GROUP

ALL PHYSICAL SAMPLES SUCH AS FINISH SAMPLES, CUTTINGS OR HARDWARE TO BE SEND TO THE FOLLOWING ADDRESS UNLESS NOTIFIED OTHERWISE.
AVENUE INTERIOR DESIGN
8322 BEVERLY BLVD., SUITE 201
LOS ANGELES, CA 90048
ATTN: MACKENZIE BERGERON
C. 818.416.4620
EMAIL: MACKENZIEB@AVENUEID.COM

SHOP DRAWINGS:
1. ALL DRAWINGS TO INCLUDE PLANS, ELEVATIONS AND SECTIONS.
2. SHOP DRAWING TO INDICATE PROJECT NAME, ISSUE DATE, SPEC NUMBER, DRAWING SCALE, OVERALL AND DETAILED DIMENSIONS, MATERIAL AND FINISHES (SOLIDS AND VENEERS), FABRICATION METHODS, ALL DECORATIVE AND MECHANICAL HARDWARE, QUANTITY AND WEIGHT.
3. WHERE APPLICABLE, CASEGOOD MFR TO SHOW SPECIFIED EQUIPMENT DIMENSIONS WITH 1" CLEARANCE ON ALL SIDES OR AS OTHERWISE REQUIRED BY APPLIANCE MFR.
4. WHERE APPLICABLE, MFR TO SHOW PERMANENT MOUNTING METHOD OF SAFE TO CASE PIECE AND CONFIRM THAT MATERIAL DOCUMENTED IS SUITABLE FOR SAFE TO BE SECURED AND ATTACHED TO SHELF OR DRAWER.

FINISH SAMPLES:
MFR TO SUBMIT 2 SETS OF ALL FINISH SAMPLES. ALL SAMPLES SHALL BE APPLIED ON APPROPRIATE SUBSTRATE AS SPECIFIED FOR THE FINAL ITEM. SAMPLES MUST BE A MINIMUM OF 4" X 4" AND MUST SIGNIFICANTLY SHOW PATTERN, REPEAT, AND ACCEPTABLE RANGE OF COLOR OR HUE. ALL FINAL FINISHES MUST MATCH APPROVED
SAMPLES.

ELEVATOR DIMENSIONS: SERVICE ELEVATOR - 68"W X 98"D X 108"H; ELEVATOR DOOR OPENING: 48"W X 84"H - MANUFACTURER TO ENSURE FURNITURE PIECE WILL FIT WITHIN ELEVATOR CAB AND THROUGH ALL DOORWAYS AND OPENINGS DURING INSTALL.

PURCHASE ORDER PROOF ONLY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:

MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)

WOOD CONSTRUCTION
-ALL WOOD MUST BE FSC CERTIFIED KILN DRIED PREMIUM HARDWOOD SOLIDS AND VENEERS AND MUST BE TREATED TO BE INSECT AND VERMIN FREE. ALL EDGES MUST BE SOLID WOOD. ALL PLYWOOD MUST BE FSC CERTIFIED AND FORMALDEHYDE FREE. MDF IS NOT ACCEPTABLE FOR USE IN WET LOCATIONS AND/OR IN AREAS WHICH MAY COME INTO CONTACT WITH WET MOP. MFR TO CONFER WITH AVEID.
-ALL JOINTS MUST BE FLUSH AND SMOOTH. ALL JOINTS MUST BE MORTISE AND TENON OR DOUBLE-DOWELED AND GLUED AT EACH SIDE. ALL DOWELS MUST BE HARDWOOD.
-THE USE OF STAPLES AND NAILS ARE NOT ACCEPTABLE. ALL CORNERS MUST BE BLOCKED, GLUED AND FASTENED WITH COUNTERSUNK SCREWS.
-ALL WOODWORK MATERIALS SHALL BE NEW AND SHALL CONFORM TO PREMIUM GRADE REQUIREMENTS. UNEXPOSED AND EXPOSED WOOD SHALL NOT CONTAIN PLUGS, KNOTS, PITCH POCKETS, SPLITS, ROUGH GRAIN OR OTHER OPEN DEFECTS.
-MFR TO PROVIDE DISCREET UTILITY CUTOUTS AND/OR GROMMETS FOR WIRE MANAGEMENT AND VENTILATION WHERE APPLICABLE. ALL ELECTRONIC EQUIPMENT TO BE APPROPRIATELY VENTILATED.
-MFR SHALL SUPPLY ALL HARDWARE BRACKETS, CLEATS, BOLTS, AND OTHER PARTS REQUIRED FOR INSTALLATION OF CASEGOODS. WHERE APPLICABLE, MFR MUST PROVIDE FRENCH CLEAT FOR WALL ATTACHMENT.
-LEGS MUST BE FABRICATED FROM ONE PIECE OF WOOD. LAMINATION OF WOOD TO EXTEND LENGTH IS NOT ACCEPTABLE. PLYWOOD IS ACCEPTABLE FOR CONTOURING, STRUCTURAL, AND SIDE FRAMING. MDF IS NOT ACCEPTABLE.
-ALL FACE SCREWS OR NAILS UTILIZED TO ATTACH TRIM ITEMS MUST BE COUNTERSUNK, WOOD PLUGS USED TO COVER HEADS MUST BE NEATLY TOUCHED UP.
- CABINET INTERIORS, DOORS AND DRAWERS MUST BE FINISHED IN THE SAME VENEER AS THE EXTERIOR.
PROVIDE HEAVY-DUTY NON-RUSTING METAL GLIDES SUITABLE FOR CARPET / METAL ADJUSTABLE LEVELERS (FOR LARGER ITEMS ESPECIALLY ITEMS WITH DOORS.) USE HAFELE
OR MFR RECOMMENDED EQUAL.

DRAWER CONSTRUTION
DRAWER SIDES MUST BE DOVETAILED OR BUTTERFLY JOINTED AND GLUED UNDER PRESSURE. DOVETAILS MUST BE MILLED TRUE AND EVEN. DRAWER INTERIORS MUST BE SANDED SMOOTH, LACQUERED AND WAXED. DRAWERS MUST HAVE REMOVABLE STOP MECHANISM FOR REPAIR OR ACCESS. PROVIDE DUST PANELS BETWEEN EACH DRAWER. DUST PANELS MUST BE NO LESS THAN 1/4" THICK HARDBOARD. ALL DRAWERS AND PULL-OUT SHELVES MUST HAVE QUALITY, HEAVY-DUTY, FULLY CONCEALED, SOFT-CLOSE, BALL BEARING, FULL EXTENSION, UNDER-MOUNTED (SIDE MOUNTED FOR SHALLOW DRAWERS) GLIDES. GLIDES MUST BE SUITABLE FOR SIZE AND WEIGHT OF DRAWER OR PULL-OUT SHELF. USE HAFELE OR MFR RECOMMENDED EQUAL.

METAL CONSTRUCTION:
WHEN SPECIFICATION CALLS FOR STAINLESS STEEL, MFR MUST SPECIFY GRADE 201 OR HIGHER. IF SPECIFYING FOR DAMP, WET, OR OUTDOOR CONDITIONS, MFR MUST SPECIFY GRADE 304 OR HIGHER. ALL JOINTS MUST BE SOLDERED FLUSH AND SMOOTH. ALL CASEGOODS TO BE ASSEMBLED WITHOUT FACE SCREWS EXCEPT WHERE IT MAY BE NECESSARY TO ATTACH TRIM ITEMS. ALL MATERIALS SHALL BE NEW.

STONE CONSTRUCTION
STONE MUST BE FREE FROM DEFECT, INCLUDING APPEARANCE, CRACK, BREAKAGE, ETC. MFR TO PROVIDE ALL HARDWARE FOR MECHANICALLY FASTENING STONE TOP TO BASE. MFR MUST CONFIRM BASE OR FRAME ARE SUFFICIENT TO SUPPORT WEIGHT OF STONE TOP.

GENERAL INFO:
1. ALL MATERIALS AND METHODS OF CONSTRUCTION MUST COMPLY WITH ALL APPLICABLE INTERNATIONAL, NATIONAL, STATE, LOCAL, AND CITY LIFE SAFETY CODES. CERTIFICATE OF COMPLIANCE TO BE SUBMITTED TO OWNER BY PRODUCT MFR.
2. ALL MATERIALS AND CONSTRUCTION MUST BE CONTRACT QUALITY AND COMPLY WITH OWNER'S STANDARDS AND SPECIFICATION.
3. ALL MATERIALS USED IN THE MANUFACTURING PROCESS RELATED TO THE CONSTRUCTION, FINISH, OR TREATMENT OF THIS ITEM MUST BE SUITABLE FOR PROJECT INSTALLATION CLIMATE (INCLUDING, BUT NOT LIMITED TO, IMPERVIOUS TO DAMAGE FROM EXPOSURE TO EXTREME TEMPERATURE OR EXTREME HUMIDITY, NOT LIABLE TO RUSTING, CORROSION, ABRASION, MILDEW, ROT, DELAMINATING, CRACKING, WARPING, OR SPLITTING, AS APPLICABLE).
4. WHERE APPLICABLE, ITEM MUST BE AS SHOWN IN CATALOG PHOTO AND DESCRIPTION, UNLESS OTHERWISE NOTED. IN THE EVENT OF A DISCREPANCY, PLEASE CONTACT AVEID / THE CARDY GROUP IMMEDIATELY FOR WRITTEN APPROVAL PRIOR TO PRODUCTION.
5. MFR TO CONFIRM PIECE FITS THROUGH ALL DOORWAYS AND OPENINGS, INCLUDING ELEVATOR DOORS AND WITHIN CAB.
6. MFR MUST COORDINATE WITH AVEID TO PROVIDE RECESSED BACK PANEL TO ALLOW ADEQUATE SPACE FOR ELECTRICAL PLUGS BEHIND PIECE. RECESSED BACK
SHOULD NOT BE VISIBLE FROM SIDES OR TOP AND PIECE SHOULD SIT FLUSH AGAINST WALL.
7. MFR MUST COORDINATE WITH AVEID TO PROVIDE BASE CUTOUT OR INSET LEGS AT BACK OF PIECE.
8. ALL CASEGOODS MUST BE PROPERLY WEIGHTED AND DIMENSIONALLY STABLE TO ENSURE ITEM WILL NOT TIP OVER. ALL CASEGOODS AND PARTS MUST BE PLUMB, LEVEL, AND SQUARE.
9. ALL SIDES (BACK, INTERIOR, ETC.) MUST BE FINISHED TO MATCH APPROVED FINISH SAMPLES UNLESS OTHERWISE SPECIFIED BY AVEID.
10. WHERE APPLICABLE, MFR MUST WELD, GRIND, CLEAN, AND POLISH ALL JOINTS. MFR MUST PROVIDE PROPER SUPPORT FOR SIZE OF SPECIFIED PIECE TO AVOID
RACKING AND TWISTING. ALL METAL (INCLUDING HARDWARE) MUST BE CORROSION RESISTANT AND RUSTPROOF.

PURCHASE ORDER COPY

1220 Yonge Street Suite 300
Toronto, ON M4T 1W1
Phone 416-421-6655 Fax 416-421-9133
www.thecardygroup.com
Buyer: MABEL HAO
mabel.hao@thecardygroup.com

PURCHASE ORDER
#1251-0051B

Issued as agent on behalf of:

MGM RESORTS DESIGN & DEVELOPMENT

Quantity	UOM	Description	Spec-Model	Unit Cost	Extended (USD)
		11. ITEMS TO BE PRODUCE PER SPEC, ALL SUBSTITUTIONS MUST BE SUBMITTED FOR WRITTEN APPROVAL PRIOR TO MANUFACTURING. 12. IN THE EVENT OF A DISCREPANCY BETWEEN DRAWINGS AND SPECIFICATIONS, PLEASE CONTACT AVEID IMMEDIATELY FOR WRITTEN CLARIFICATION.			

Instructions :

IMPORTANT NOTE:
- ALL PRICES STATED IN THIS PURCHASE ORDER ARE FIRM, FIXED AND NOT SUBJECT TO INCREASE FOR ANY REASON, INCLUDING BUT NOT LIMITED TO CHANGES IN TARIFFS, DUTIES, TAXES, SURCHARGES OR CURRENCY FLUCTUATIONS UNLESS OTHERWISE AGREED BY THE CARDY GROUP OR MGM RESORTS DESIGN & DEVELOPMENT PROCUREMENT TEAM IN WRITING.
- ALL ABOVE PRICES INCLUDE DUTY/TARIFF COSTS ****GOODS TO BE LANDED, DUTIES AND BROKERAGE PAID
- ALL GOODS TO BE INSURED FOR FULL REPLACEMENT VALUE
- MANUFACTURER AS LISTED ON THIS PURCHASE ORDER IS THE IMPORTER OF RECORD
- NO COMPANY LOGOS ON FURNITURE PIECES
- SUBMITTALS SUPERCEDE PURCHASE ORDER

All PARTIES ARE RESPONSIBLE FOR READING & ADHERING TO THE GUIDELINES BELOW;
GENERAL
- All items must be of contract quality, suitable for commercial hospitality use.
- All items must be provided with a minimum 2 year full warranty.
- All shipments to be fully insured for full replacement value
- Invoices for the purchase of fabric, carpet and wallcovering must be accompanied by a flame certificate stating the rating of goods purchased, plus a copy of the recommended cleaning instructions and warranty information.
- Note subsequent reviews, comments and approvals of shop drawings, finish samples, CFA's (cuttings for approval), samples, models, strike-offs, etc., supersedes the description details on the purchase order.

INVOICE/PAYMENT PROCESSING
(Invoices with incorrect / incomplete information will be subject to payment delays)
- Submit invoice for deposit payment on receipt of this purchase order. Taxes should not be charged on deposits.
- Each purchase order requires its own invoice. Payment will not be issued for invoices that combine items from more than one purchase order.
- Freight invoice must be accompanied by a copy of the actual freight bill when charge exceeds $200.00
- Invoice must match the current purchase order price and quantity. No manual changes or alterations to the invoice will be accepted.
- Deposits paid are to be reflected on and deducted from all progress and balance due payment requests.
- SALES TAX; if vendor is charging sales tax then invoice should include tax percentage and type of tax charged.
- GST/HST & VAT; vendors GST/HST # and/or TAX ID# must appear on invoice
- Final invoice must be accompanied by the bill of lading in order to be processed and paid.
- Invoices (all) should clearly state the following;
  - Payment currency
  - Bill to entity, billing address and shipping address as indicated on purchase order
- Wire transfer requires vendor banking information.
- The Cardy Group (or client) is not responsible for wire fees debited by beneficiaries' bank or intermediary banks upon receiving payment.

FREIGHT AND SHIPPING
- All product packaging must include clear tagging indicating the following information:
  - Project name
  - Product description
  - Spec/Item number
  - TCG PO Number
  - Vendor name
- Package goods to ensure they are suitable for any/all modes of transportation. Wooden pallets, crates, and/or packaging must comply with international shipping standards.
- Packaging costs must be provided in advance of packaging/shipping. Extra charges for crating, palletizing, wrapping, etc. will not be accepted.

The following documents must accompany EACH shipment:
1. Commercial invoice and/or
2. Bill of lading / airway bill (issued by freight forwarder)
3. Copy of TCG purchase order

Final Destination & End Use: Atlantic City, NJ 08401, United States

PURCHASE ORDER PROOF ONLY

ALL PRICES IN USD EXCLUDING TAXES **Total** **942,581.40**